



NOTES:

- 1) POST WITH EYE HOOKS REQUIRED FOR CHAINING AND LOCKING THE CONSTRUCTION METER.
- 2) FOR INSTALLATION TO A FIRE HYDRANT, THE METER SHALL BE INSTALLED DIRECTLY TO THE 2-1/2" HYDRANT PORT. THE CUSTOMER IS RESPONSIBLE TO INSTALL THE PRIVATE VALVE ON THE TEMPORARY CONSTRUCTION METER AND BACKFLOW PER W-19.

REVISIONS			VALLECITOS WATER DISTRICT STANDARD DRAWING	DATE: 2-27-18
DESCRIPTION	APPROVED	DATE		BY: P.C.
NEW MAP		2-28-18	CONSTRUCTION METER ON A BLOW-OFF	Drawing No.
ADDED NOTE 2		7-27-22		W-0